



Road Pavement Restoration Works Panel Contract



shepherdservices.com.au



Contract Context

Contract No. 1695006

Flood and storm event

September 2022 onwards

Damaged roads

Damaged municipal infrastructure

CSC working with NSW Government

CSC working with Shepherd



Contract Overview

Contract No. 1695006

Repair damaged roads

Panel contract – AS4000 GCoC

Schedule of rates

In situ stabilisation

Patch repair / reconstruction

PC date 30 June 2025

Possible panel contract extension if required

Contract Overview

Contract No. 1695006

Current budget

Approved works total \$7 - \$8m

Further approvals being sought \$12 - \$17m

Possible total \$20 - \$25m

Contract Overview

Contract No. 1695006

Insitu Stabilisation – ST6

- Pulverisation of existing road surface.
- Removal of material not suitable for stabilisation.
- Importation and spreading of unbound granular material to replace unsuitable material.
- Pulverisation.
- Supply and spreading of stabilising agents.
- Stabilisation of granular material at a rate of 2% by mass of stabilised material.
- Compaction, trimming and curing of stabilised granular material; and.
- Two coat bitumen seal.

Part 3 – Contract Specific Clauses 1.2 Scope of Work

Currently approved approx. 8,800m²

Contract Overview

Contract No. 1695006

Reconstruct Pavement – ST8

- Removal of failed or damaged pavement material;
- Allowance for replacement of unsuitable subgrade material;
- Compaction of subgrade;
- Importation of granular material;
- Provision of onsite stockpiles (if required);
- Placement, compaction and trimming of unbound granular material in layers to match adjoining; and
- Two coat bitumen seal.

Part 3 – Contract Specific Clauses 1.2 Scope of Work – to be included

Currently approved approx. 1,000m²

Contract Overview

Contract No. 1695006

Patch Repair – ST9

- Removal and reconstruction of isolated pavement failures.
- Removal of failed pavement material.
- Reasonable allowance for replacement of unsuitable subgrade material.
- Compaction of subgrade.
- Importation of granular material.
- Placement, compaction and trimming of unbound granular material in layers to match adjoining; and.
- Two coat bitumen seal.

Part 3 – Contract Specific Clauses 1.2 Scope of Work

Currently approved approx. 6,900m²

Contract Overview

Contract No. 1695006

Tender/Contract Timeframes

Tender advertised – Wednesday 29 May

Tender Questions – Wednesday 19 June

Tender closing – 12 Noon Wednesday 26 June

Tender Evaluation – June/July

Intended Council resolution date – 23 July

Intended contract commencement – August

Contract Pricing

Contract No. 1695006

Attachment 2 – Pricing Schedule

Quantities – Schedule tender assessment only

Quantities – Provisional fixed

Provisional – Sum fixed amount



Contract Pricing

Contract No. 1695006

Attachment 3 – Schedule of Rates for Additional Works

For pricing additional works approved by the
Superintendent

Plant, equipment and personnel



Contract Assessment

Contract No. 1695006

Evaluation criteria Part 1 Clause 6 Evaluation Criteria

Mandatory criteria – Yes/No

Quantative criteria – Pricing/ Schedule of Rates

Qualitative criteria – Ability to complete contract works and local benefit

Contract Operation

Contract No. 1695006

CSC completing some works

CSC working in advance of contractor

Work packages

Work package pricing

Work package timing

Work package value

Contract Operation

Contract No. 1695006

Dayworks

Provisional Quantity items

- 2.1 Unsuitable subgrade material
- 2.2 Unsuitable pavement material
- 2.3 Insitu subgrade rehabilitation
- 2.4 Mobilisation to site
- 2.5 Demobilisation from site

Contract Operation

Contract No. 1695006

Pricing Schedule items

3.3 Unsuitable material

3.3.3 Supply and place pavement material

3.3.4 Supply and place geotextile material

3.3.5 Increase / decrease binder application rate

Contract Operation

Contract No. 1695006

Pricing Schedule items

3.4 Other works

3.4.1 Supply and install guideposts

3.4.2 Supply, operate and maintain traffic lights

3.4.3 Supply, operate and maintain VMS board

Contract Operation

Contract No. 1695006

Material supply

Contractor to supply material

Local pits and quarries should be used



Contract Changes

Contract No. 1695006

Document Changes

CSC 1.2 Scope of Work – Inclusion of ST8 treatment requirements

CSC 5.4 Guideposts – Clarification of what works unit rate covers

CSC 6.6 Variations – Clause deleted

CSC 6.7 (new) (6.8 old) Measurement and Payment Provisional Sums and Quantities – Addition of profit to pricing inclusions

CSC 6.8 (new) (6.9 old) Measurement and Payment Schedule of Rates Items – clarification excluding provisional items

Tender Period

Contract No. 1695006

Tender instructions

Clause 8 Nominated Council Officer

Ben Howad – Contacted via CSC and Mark Ellis

Documents to submit



Contract General

Contract No. 1695006

Questions



Thank You



shepherdservices.com.au